

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20484-00-00
Spot: NWSWNESE Sec/Twnshp/Rge: 8-32S-31W
1958 feet from S Section Line, 1309 feet from E Section Line
Lease Name: ROEHR Well #: 1-8
County: SEWARD Total Vertical Depth: 5993 feet

Operator License No.: 31021
Op Name: CASTELLI EXPLORATION, INC.
Address: 6908 W 112TH
OKLAHOMA CITY, OK 73162

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5428		WITH 2 SX CMT
PROD	4.5	5727	1637	WITH 200 SX CMT
SURF	8.625	1600		WITH 750 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/21/2013 12:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: CIBP @ 5430' & 2 SX CMT. PLUG AT 1630' WITH 20 SX GEL & 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: NATHAN WILLIS WitnessType: NONE
Date/Time Plugging Completed: 11/21/2013 2:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SET CIBP @ 5428' WITH 2 SX CMT. 1ST PLUG AT 1639' WITH 20 SX GEL & 50 SX CMT. 2ND PLUG AT 567' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5546	5550		
5484	5490		

Remarks: **COMPLIANCE ISSUE: NOV TA LTR** USED 60/40 POZMIX 4% GEL.

Plugged through: TBG

District: 01

Signed Nathan Willis

(TECHNICIAN)

RECEIVED

DEC - 3 2013

KCC DODGE CITY

12/20/2013

KCC WICHITA

DEC 09 2013

RECEIVED

Form CP-2/3