

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-081-20076-00-00
Spot: SW Sec/Twnshp/Rge: 16-30S-31W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: ELLSAESSER Well #: 1-16
County: HASKELL Total Vertical Depth: 2750 feet

Operator License No.: 32334
Op Name: CHESAPEAKE OPERATING, INC.
Address: 6200 N WESTERN AVE PO BOX 18496
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2600		WITH 2 SX CMT
PROD	4.5	2696	0	WITH 685 SX CMT
SURF	8.625	504		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/25/2013 8:30 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STEVE EMICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/25/2013 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 2600' WITH 2 SX CMT. RAN BOND LOG. TOC @ 478'. PEFORATE AT 473'.
FILL 4 1/2" CASING WITH CMT FROM 2580' TO 0' IN 3 STAGES THROUGH TBG
USING A TOTAL OF 130 SX CMT. CIRCULATE CMT FROM 473' TO 0' IN THE 4 1/2" X
8 5/8" ANNULUS USING 70 SX CMT.

Perfs:


Top	Bot	Thru	Comments
2674	2684		

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED

DEC - 3 2013

KCC DODGE CITY

KCC WICHITA

DEC 12 2013

RECEIVED

Form CP-2/3

