

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-23252-00-00
Spot: NENWSWNW Sec/Twnshp/Rge: 2-33S-13W
3881 feet from S Section Line, 506 feet from W Section Line
Lease Name: MAGNISON A Well #: 1
County: BARBER Total Vertical Depth: 5018 feet

Operator License No.: 33235
Op Name: CHIEFTAIN OIL CO., INC.
Address: 101 S. 5TH ST. PO BOX 124
KIOWA, KS 67070

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4400		WITH 2 SX CMT
PROD	5.5	5015	2300	WITH 200 SX CMT
SURF	8.625	300		WITH 275 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 11/25/2013 9:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MORGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 4400' & 2 SX CMT. PLUG AT 660' WITH 10 SX GEL & 50 SX CMT. PLUG AT 330' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: PARTIAL
Date/Time Plugging Completed: 11/25/2013 10:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 4400' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 682' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 342' WITH 50 SX CMT. 3RD PLUG AT 62' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4458	4468		
4450	4454		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

KCC WICHITA

DEC 06 2013

RECEIVED

District: 01

Signed Richard W. Fox

(TECHNICIAN)

RECEIVED

DEC - 3 2013

KCC DODGE CITY

✓ 12/20/2013