

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-03278-00-00  
Spot: SESENW Sec/Twnshp/Rge: 10-10S-25W  
2970 feet from S Section Line, 2970 feet from E Section Line  
Lease Name: ELRICK Well #: 11-1  
County: GRAHAM Total Vertical Depth: 4019 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3725		
PROD	5.5	4018		150 SX
SURF	8.625	192		130 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2013 11:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: \_\_\_\_\_ Company: EXPRESS WELL SERVICE & SUPPL Phone: (281) 891-1000

Proposed Plugging Method: Ordered 650 sx 60/40 pozmix 4% gel cement w/600 # hulls.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/26/2013 4:30 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Casing parted at 2254'. Shot tubing off at that point and left packer stuck in hole at 2254'. Bottom perforations at 3375' - 3999'. Shot new perforations at 1275' - 1278' and 185' - 188'. Ran tubing to 2240' and pumped 650 sx cement w/450 # hulls. Got returns out of casing and backside after pumping 600 sx cement. Ran out of cement. Truck went back to Oakley for more cement. Tom Culley finished plugging. Trucks returned with more cement and pumped 100 sx cement w/200 # hulls. Good circulation of cement out of casing and backside. Hole standing full.

Perfs:


Top	Bot	Thru	Comments
3775	3999		

Remarks: ALLIED CEMENT TICKET # 61197

Plugged through: TBG

District: 04

Signed

  
(TECHNICIAN)

CM

✓ 12/20/2013

KCC WICHITA

Form CP-2/3

DEC 02 2013

DEC 09 2013

RECEIVED