

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-21477-00-00
Spot: SESENW Sec/Twnshp/Rge: 17-15S-12W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: SOUKUP Well #: 1-B
County: RUSSELL Total Vertical Depth: 3320 feet

Operator License No.: 31341
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA
Address: 15 S MAIN
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3319		
SURF	8.62	213		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/20/2013 3:00 PM
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.
Proposal Rcvd. from: WARD CRAIG Company: CRAIG OIL CO. Phone: (785) 483-1543

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement and 400 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/20/2013 6:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 200', 782' and 1250'. Ran tubing to 3180' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1930' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 680' and pumped 75 sx cement. Cement circulated out back side. POOH. Hooked to casing and pumped 45 sx cement. Cement circulated out braden head. Shut in and pressured casing to 400 psi.

GPS: 38.74859 -098.68103

Perfs:

Top	Bot	Thru	Comments
3315	3318		
3150	3160		

Remarks: QUALITY CEMENTING TICKET # 7017

Plugged through: TBG

KCC WICHITA

DEC 04 2013

RECEIVED

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

NOV 25 2013

✓ 12/20/2013