

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21597-00-00  
Spot: W2SEW Sec/Twnshp/Rge: 17-15S-12W  
3300 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SOUKUP Well #: 2  
County: RUSSELL Total Vertical Depth: 3385 feet

Operator License No.: 31341  
Op Name: CRAIG, WARD DBA CRAIG OIL COMPA  
Address: 15 S MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3321		125 SX
SURF	8.62	241		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/20/2013 8:30 AM  
Plug Co. License No.: 33385 Plug Co. Name: J & M WELL SERVICING, INC.  
Proposal Rcvd. from: WARD CRAIG Company: CRAIG OIL CO. Phone: (785) 483-1543

Proposed Plugging Method: Ordered 280 sx 60/40 pozmix 4% gel cement and 200 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 11/20/2013 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 200', 785' and 1250'. Ran tubing to 3200' and pumped 100 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 75 sx cement. Cement circulated. POOH. Hooked to casing and pumped 75 sx cement. Circulated cement to pit through braden head and filled cellar.

GPS: 38.74948 -098.68335

Perfs:

Top	Bot	Thru	Comments
3331	3334		

Remarks: QUALITY CEMENTING TICKET # 7015

Plugged through: TBG

District: 04

Signed

*Ray Dinkel*

(TECHNICIAN)

CM

NOV 25 2013

*12/20/2013*

KCC WICHITA

DEC 04 2013

RECEIVED

Form CP-2/3