

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-21182-00-01
Spot: NENWNENW Sec/Twnshp/Rge: 11-23S-16E
5055 feet from S Section Line, 3512 feet from E Section Line
Lease Name: WEBB A (WEST) Well #: 3
County: COFFEY Total Vertical Depth: 1001 feet

Operator License No.: 4567
Op Name: D. E. EXPLORATION, INC.
Address: PO BOX 128
WELLSVILLE, KS 66092

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1001		120 SX
SURF	7	0		
SURF	7	41		10 SX

Well Type: EOR UIC Docket No: E27879.2 Date/Time to Plug: 12/04/2013 10:30 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: HARVEY FRANCIS Company: Phone: (785) 883-4057

Proposed
Plugging
Method:

Wash well through 1" tubing to TD, cement well through 1" tubing from bottom to top.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2013 1:30 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran 1" to 940' pumped 10 sxs cement, pulled tubing to 550' pumped 10 sxs cement, pulled tubing to 250' pumped 30 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
970	976		

RECEIVED
DEC 09 2013
KCC Chanute Dist. #3
MH

Remarks:

Plugged through: TBG

District: 03

Signed Mike P. [Signature]
(TECHNICIAN)

CC to UIC
✓ 12/20/2013

KCC WICHITA

Form CP-2/3

DEC 11 2013

RECEIVED

10:30-#30

Hurricane Services, Inc.

3613 A Y Road

Madison, KS 66860

Office # 620-437-2661

Brad Cell # 620-437-6765

15-031-21182-00-01



HURRICANE SERVICES INC
OILFIELD SERVICES
MADISON, KANSAS

Ticket Number 100342

Location Madison

Foreman Brad Butler

Cement Service ticket

Date	Customer #	Well Name & Number	Sec./Township/Range	County
12-4-13		Webb "A" #3	11-23s-16E	Coffey
Customer		Mailing Address	City	State Zip
D.E. Exploration, Inc.				

Job Type:	<u>Plug To Abandon</u>		Truck #	Driver
Hole Size:	Casing Size: <u>4 1/2"</u>	Displacement:	<u>201</u>	<u>Kelly</u>
Hole Depth:	Casing Weight:	Displacement PSI:	<u>203</u>	<u>Jelly</u>
Bridge Plug:	Tubing:	Cement Left in Casing:	<u>106</u>	<u>Bryon</u>
Packer:	PBTD: <u>1000'</u>			

Quantity Or Units	Description of Services or Product	Pump charge	
<u>0</u>	Mileage	\$3.25/Mile	<u>600.00</u>
			<u>N/C</u>
<u>50 SACKS</u>	<u>60/40 Pozmix cement</u>	<u>12.00</u>	<u>600.00</u>
<u>130 lbs.</u>	<u>Gel 3%</u>	<u>.30</u>	<u>39.00</u>
<u>100 lbs.</u>	<u>Gel Spacer</u>	<u>.30</u>	<u>30.00</u>
<u>2 Hrs.</u>	<u>WATER TRUCK</u>	<u>84.00</u>	<u>168.00</u>
<u>Tons</u>	<u>Bulk Truck 2nd well of 4</u>	101.25	<u>101.25</u>
	Plugs		
		Subtotal	<u>1538.25</u>
		Sales Tax <u>6.15%</u>	<u>41.14</u>
		Estimated Total	<u>1579.39</u>

Remarks: Set cement plugs as follows:

10 SKs at 940'
10 SKs at 550'
30 SKs at 250' To Surface

KCC WICHITA
DEC 11 2013

NOTE: washed tubing to bottom - circulated well clean before cementing process

RECEIVED

witnessed by Harvey

Customer Signature