

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-031-21309-00-01
Spot: SENENWNW Sec/Twnshp/Rge: 11-23S-16E
4691 feet from S Section Line, 4173 feet from E Section Line
Lease Name: WEBB A (WEST) Well #: 5
County: COFFEY Total Vertical Depth: 1019 feet

Operator License No.: 4567
Op Name: D. E. EXPLORATION, INC.
Address: PO BOX 128
WELLSVILLE, KS 66092

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	1011		120 SX
SURF	7	84		32 SX

Well Type: EOR UIC Docket No: E27879.3 Date/Time to Plug: 12/04/2013 1:30 PM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: HARVEY FRANCIS Company: Phone: (785) 883-4057

Proposed Plugging Method: Wash well through 1" tubing to TD, cement well through 1" tubing from bottom to top.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/04/2013 3:30 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran 1" tubing to 970' pumped 10 sxs cement, pulled tubing to 550' pumped 10 sxs cement, pulled tubing to 250' pumped 25 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
963	971		
RECEIVED DEC 09 2013 KCC Chanute Dist. #3 MH			

Remarks:

Plugged through: TBG

District: 03

Signed Mike D. (TECHNICIAN)

cc to UIC
✓ 12/20/2013

KCC WICHITA

Form CP-2/3

DEC 11 2013

RECEIVED

1:30-3:30
 Hurricane Services, Inc.
 3613 A Y Road
 Madison, KS 66860
 Office # 620-437-2661
 Brad Cell # 620-437-6765



HURRICANE SERVICES INC
 OILFIELD SERVICES
 MADISON, KANSAS

Ticket Number 100343
 Location Madison
 Foreman Brad Butler

15-031-21309-00-01

Cement Service ticket

Date	Customer #	Well Name & Number	Sec./Township/Range	County
12-4-13		Webb 'A' #5	11-23s-16E	Coffey
Customer		Mailing Address	City	State Zip
D.E. Exploration, Inc.				

Job Type:	Truck #	Driver
Plug To Abandon	201	Kelly
Hole Size:	203	Jerry
Casing Size: 4 1/2"	106	Bryan
Hole Depth:		
Casing Weight:		
Displacement PSI:		
Bridge Plug:		
Tubing:		
Cement Left in Casing:		
Packer:		
PBTD: 1010'		

Quantity Or Units	Description of Services or Product	Pump charge	
0	Mileage	\$3.25/Mile	N/C
45 SACKS	60/40 Pozmix Cement	12.00	540.00
115 lbs.	Gel 3%	.30	34.50
100 lbs.	Gel Spacer	.30	30.00
2 Hrs.	WATER TRUCK	84.00	168.00
Tons	Bulk Truck > 3 rd well of 4	101.25	101.25
	Plugs		
		Subtotal	1473.75
	6.152	Sales Tax	37.17
		Estimated Total	1510.92

Remarks: Set cement Plugs as following:

10 SKS @ 970'
 10 SKS @ 550'
 25 SKS @ 250' To Surface

KCC WICHITA
 DEC 11 2013
 RECEIVED

NOTE: Washed Tubing down to bottom - circulated well clean before cementing

Witnessed by Hervey
 Customer Signature