

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-22335-00-00
Spot: S2SWSW Sec/Twnshp/Rge: 12-31S-12W
297 feet from S Section Line, 4635 feet from E Section Line
Lease Name: MOTT F Well #: 27
County: BARBER Total Vertical Depth: 4400 feet

Operator License No.: 3372
Op Name: DIXON ENERGY, INC.
Address: 8100 E 22ND N BLDG 300, STE 200
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3320		WITH 2 SX CMT
PROD	4.5	3502	2700	WITH 150 SX CMT
SURF	8.625	292		WITH 300 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 12/11/2013 8:30 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: TJ DIXON Company: DIXON ENERGY Phone: (316) 264-9632

Proposed Plugging Method: SET CIBP @ 3320' & 2 SX CMT. PLUG AT 600' WITH 10 SX GEL & 50 SX CMT. PLUG AT 320' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/11/2013 10:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 3320' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. 1ST PLUG AT 598' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 310' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3378	3390		

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

DEC 18 2013
RECEIVED

Plugged through: TBG

District: 01

Signed Stephen J. P... (TECHNICIAN)

RECEIVED
DEC 12 2013
KCC DODGE CITY

✓ 12/20/2013

AWZ