

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-22710-00-00  
Spot: E2SESE Sec/Twnshp/Rge: 17-15S-12W  
660 feet from S Section Line, 330 feet from E Section Line  
Lease Name: LEURMEN - C Well #: 6  
County: RUSSELL Total Vertical Depth: 3325 feet

Operator License No.: 31070  
Op Name: EAGLE RIVER ENERGY CORPORATIO  
Address: 7060 S YALE # 702  
TULSA, OK 74136

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3240		
PROD	4.5	3324		125 SX
SURF	8.625	634		280 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2013 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: JOHN MICKLE Company: EAGLE RIVER ENERGY CORP Phone: (620) 282-9034

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement and 300 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/15/2013 11:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

Had holes at 640' and 1475'. Cement on backside was checked by Ray Dinkel on 11/14/2013. TOC was 6'.  
Ran tubing to 3050' and pumped 100 sx cement w/150 # hulls. Pulled tubing to 1525' and pumped 110 sx cement w/150 # hulls. Cement circulated. POOH. Hooked to casing and pumped 20 sx cement at 250 psi. Shut in. The surface pipe was filed with cement when pulling tubing.  
11/20/2013-Topped off casing w/15 sx of dry cement and 2 bbls of water.  
GPS: 38.74225 -098.67185

Perfs:

Top	Bot	Thru	Comments
3277	3291		
3042	3164		

Remarks: ALLIED CEMENTING INC. TICKET # 54850

Plugged through: TBG

District: 04

Signed Ray A. Dinkel  
(TECHNICIAN)

CM

NOV 25 2013

12/20/2013

KCC WICHITA

Form CP-2/3

DEC 04 2013

RECEIVED