

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21564-00-00
Spot: NESWSE Sec/Twnshp/Rge: 4-18S-12W
990 feet from S Section Line, 1650 feet from E Section Line
Lease Name: WIRTH C Well #: 1
County: BARTON Total Vertical Depth: 3348 feet

Operator License No.: 34434
Op Name: EDISON OPERATING COMPANY LLC
Address: 8100 E. 22ND ST. N., BLDG 1900
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3338		125 SX
SURF	8.625	209		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/13/2013 1:00 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: ROCH MILLER Company: EDISON OPERATING Phone: (620) 786-5161

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 500 # hulls and 14 sx gel.

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2013 4:30 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1300', 720' and 180'. Ran tubing to 3307' and pumped 14 sx gel followed by 50 sx cement and 100 # hulls. Pulled tubing to 1356' and pumped 70 sx cement w/100 # hulls. Pulled tubing to 740'. Circulated cement to surface with 240 sx cement and 150 # hulls on casing and surface pipe. Pulled tubing and topped off with 15 sx cement.

GPS: 38.51015 -098.65167

Perfs:

Top	Bot	Thru	Comments
3338	3348		
3082	3330		

Remarks: ALLIED CEMENTING

Plugged through: T36
CSG

KCC WICHITA

DEC 04 2013

RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

NOV 25 2013

✓ 12/20/2013