

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-07057-00-00
Spot: NWNENENE Sec/Twnshp/Rge: 28-14S-14W
4955 feet from S Section Line, 400 feet from E Section Line
Lease Name: OLSON A J - B Well #: 1
County: RUSSELL Total Vertical Depth: 3301 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
L1	4.5	3298		125 SX
PROD	7	2979		50 SX
SURF	20	160		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/05/2013 8:30 AM
Plug Co. License No.: 6123 Plug Co. Name: CHASE WELLL SERVICE, INC.
Proposal Rcvd. from: DALTON POPP Company: EMPIRE ENERGY Phone: (316) 313-4395

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 10 sx gel, 500 # hulls, and 3 sx C.C.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/05/2013 12:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforations: 1400', 700' and 400'.
Braden head was dug out on 12/04/2013 and witnessed by Ray Dinkel to be full of cement.
Ran tubing to 2910' and pumped 6 sx gel followed by 75 sx "hot" cement w/100 # hulls. Pulled tubing to 2030' and pumped 4 sx gel followed by 125 sx "hot" cement w/300 # hulls. Pulled tubing to 850' and pumped 75 sx cement w/100 # hulls. Pulled tubing to 425' and pumped 80 sx cement. Cement circulated. POOH. Hooked to casing and pumped 40 sx cement at 350 psi. Shut in.

GPS: 38.81186 -098.87474

Perfs:

Top	Bot	Thru	Comments
3222	3248		
3212	3234		
3016	3146		

Remarks: QUALITY

Plugged through: TBG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

12/20/2013

KCC WICHITA

Form CP-2/3

DEC 16 2013

RECEIVED

DEC 10 2013