

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-007-22722-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 3-30S-14W  
983 feet from N Section Line, 441 feet from W Section Line  
Lease Name: DAVIS, MABLE Well #: 1-3  
County: BARBER Total Vertical Depth: 4725 feet

Operator License No.: 5056  
Op Name: F. G. HOLL COMPANY L.L.C.  
Address: 9431 E CENTRAL STE 100  
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2150		WITH 2 SX CMT
CIBP		2600		
CIBP		4480		
PROD	4.5	4711	0	WITH 400 SX CMT
SURF	13.375	220		WITH 250 SX CMT

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/25/2013 8:00 AM  
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.  
Proposal Rcvd. from: ADAM APSLEY Company: F.G. HOLL Phone: (620) 793-0915

Proposed Plugging Method: SET CIBP @ 2150' WITH 2 SX CMT. PERFORATE @ 800' & CIRCULATE CMT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: PARTIAL  
Date/Time Plugging Completed: 11/25/2013 10:30 AM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SET CIBP @ 2150' WITH 2 SX CMT ON TOP. PERFORATED 4 1/2" @ 800'. RAN TBG TO 810' & PUMPED 350 SX CMT. CIRCULATED CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS & UP 4 1/2" CASING. PULLED TBG OUT OF HOLE & TOPPED IT OFF WITH 4 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4518	4535		
2198	2234		

KCC WICHITA  
DEC 06 2013  
RECEIVED

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA SI 10 YRS\*\* USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED

DEC - 3 2013

KCC DODGE CITY

Signed

*Richard W. Lacey*

(TECHNICIAN)

✓ 12/20/2013

*AWZ*