

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21871-00-00
Spot: N2SWSW Sec/Twnshp/Rge: 15-30S-13W
969 feet from S Section Line, 650 feet from W Section Line
Lease Name: DAVIS X Well #: 1-15
County: BARBER Total Vertical Depth: 4680 feet

Operator License No.: 5056
Op Name: F. G. HOLL COMPANY L.L.C.
Address: 9431 E CENTRAL STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3050		WITH 2 SX CMT
CIBP		4080		
PROD	4.5	4679	0	WITH 420 SX CMT
SURF	8.625	431		WITH 350 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 11/26/2013 11:00 AM
Plug Co. License No.: 8253 Plug Co. Name: G & L WELL SERVICE, INC.
Proposal Rcvd. from: ADAM APSLEY Company: F.G HOLL Phone: (620) 793-0915

Proposed Plugging Method: SET CIBP @ 3305' WITH 2 SX CMT ON TOP. PERFORATE 4 1/2" @ 730'. CIRCULATE CMT TO SURFACE UP ALL STRINGS FROM 730' TO SURFACE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/26/2013 1:00 PM KCC Agent: NATHAN WILLIS

Actual Plugging Report:

SET CIBP @ 3050' WITH 2 SX CMT ON TOP. PERFORATED 4 1/2" @ 730'. RAN TBG TO 740.5' & PUMPED 200 SX CMT. CIRCULATED CMT TO SURFACE UP 8 5/8" X 4 1/2" ANNULUS & UP 4 1/2" CASING. PULLED TBG OUT OF HOLE & TOPPED OFF WITH 7 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3355	3358		

Remarks: **COMPLIANCE ISSUE: DENIED TA SI 10 YRS** USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

Signed Nathan Willis
(TECHNICIAN)

RECEIVED

DEC - 3 2013

KCC DODGE CITY

12/20/2013

KCC WICHITA

DEC 09 2013

RECEIVED

Form CP-2/3