

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25830-00-00
Spot: NESWSENE Sec/Twnshp/Rge: 28-18S-13W
2022 feet from N Section Line, 725 feet from E Section Line
Lease Name: DOONAN 'A' Well #: 3
County: BARTON Total Vertical Depth: 3500 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3376	2260	135 SX
SURF	8.62	706		350 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2013 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GERALD ACHATZ Company: H & D EXPLORATION Phone: (620) 653-4791

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2013 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report: _____ Perfs: _____

Sanded off perforations and topped with 5 sx cement. Cut casing at 2260'. Pulled casing to 1500' and pumped 125 sx cement w/300 # hulls. Pulled casing to 750' and pumped 50 sx cement w/100 # hulls. Pulled casing to 350'. Circulated cement to surface with 125 sx cement and 200 # hulls. Pulled casing. Hole stayed full.
GPS: 38.45797 -098.75903

Remarks: COPELAND ACID AND CEMENTING
Plugged through: CSG

KCC WICHITA
DEC 09 2013
RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN) (M)

✓ 12/20/2013

DEC 05 2013