

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25281-00-00
Spot: NWNWSESW Sec/Twnshp/Rge: 4-17S-14W
1000 feet from S Section Line, 1530 feet from W Section Line
Lease Name: K-C Well #: 1
County: BARTON Total Vertical Depth: 3520 feet

Operator License No.: 34674
Op Name: H & D EXPLORATION LLC
Address: 165 WEST 1ST PO BOX 387
HOISINGTON, KS 67544

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	3505	2207	190 SX
SURF	8.62	452		300 SX
T1	2	3400		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/02/2013 11:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: GERALD ACHATZ Company: H & D EXPLORATION Phone: (620) 653-4791

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/02/2013 4:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Sanded off perforations and topped off with 5 sx cement. Cut casing at 2207'. Pulled casing to 1550' and pumped 125 sx cement w/300 # hulls. Pulled casing to 975' and pumped 50 sx cement w/100 # hulls. Pulled casing to 475'. Circulated cement to surface with 175 sx cement w/200 # hulls. Pulled casing. Hole stayed full.

GPS: 38.59639 -098.88039

Perfs:

Top	Bot	Thru	Comments
3408	3412		
3386	3390		
3336	3340		

Remarks: COPELAND ACID AND CEMENTING TICKET # 340614

Plugged through: CSG

KCC WICHITA

DEC 09 2013

RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

✓ 12/20/2013

Form CP-2/3

DEC 05 2013