

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04410-00-01
Spot: SWSWNWNE Sec/Twnshp/Rge: 9-16S-14W
4212 feet from S Section Line, 2420 feet from E Section Line
Lease Name: NUSS Well #: 2
County: BARTON Total Vertical Depth: 3409 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3407		125 SX
SURF	8.625	212		150 SX

Well Type: EOR UIC Docket No: E24878.1 Date/Time to Plug: 11/13/2013 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GEORGE PAYNE Company: HERMAN LOEB Phone: (618) 943-2227

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 800 # hulls.
Well has dv tool at 450' completed with 200 sx cement.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/13/2013 12:00 AM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Ran tubing to 3299' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 2320' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 1320'. Circulated cement to surface with 135 sx cement and 300 # hulls. Pulled tubing. Topped off with 5 sx cement. Hole stayed full.
GPS: 38.67827 -098.87595

Perfs:

Top	Bot	Thru	Comments
3300	3331		
450			

Remarks: ALLIED CEMENTING
Plugged through: CSG

KCC WICHITA
DEC 04 2013
RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN) CM

cc to UIC
✓ 12/20/2013

NOV 25 2013