

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-167-21575-00-00  
Spot: NESE Sec/Twnshp/Rge: 14-15S-14W  
1980 feet from S Section Line, 660 feet from E Section Line  
Lease Name: TITTEL - E Well #: 8  
County: RUSSELL Total Vertical Depth: 3334 feet

Operator License No.: 33813  
Op Name: JASON OIL COMPANY, LLC  
Address: 3718- 83RD ST PO BOX 701  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3329	1600	250 SX
SURF	8.625	715		400 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/26/2013 11:30 AM  
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.  
Proposal Rcvd. from: JIM SCHONEBERGER Company: JASON OIL CO. Phone: (785) 483-4204

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement w/400 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 11/26/2013 3:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perfs:

Cut 5 1/2" casing at 1600' leaving 1729' of casing in hole.  
11/25/13-Sanded off bottom and placed 5 sx cement on top.  
11/26/13-Cut casing at 1600'. Pulled casing to 1450' and pumped 125 sx cement w/300 # hulls.  
Pulled casing to 750' and pumped 50 sx cement. Pulled casing to 450' and pumped 120 sx cement. Cement circulated. POOH. Cellar stayed full of cement.

GPS: 38.74603 -098.83908

Remarks: QUALITY CEMENTING TICKET # 7020

Plugged through: CSG

District: 04

Signed

Ray Dinkel

(TECHNICIAN)

CM

12/20/2013

KCC WICHITA

DEC 12 2013

RECEIVED

Form CP-2/3

DEC 09 2013