

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-25198-00-00
Spot: NENWNESE Sec/Twnshp/Rge: 26-16S-12W
2530 feet from S Section Line, 725 feet from E Section Line
Lease Name: DOLECHEK Well #: 1
County: BARTON Total Vertical Depth: 3370 feet

Operator License No.: 9951
Op Name: KRIER, KIRBY OIL, INC.
Address: 1043 NE 80TH RD
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		3335		
PROD	5.5	3369		200 SX
SURF	8.62	370		180 SX
TI	2.875	3335		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/19/2013 8:00 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: JIM Company: KIRBY OIL INC. Phone: (620) 562-7637

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement and 500 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/19/2013 5:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

11/18/2013- Sanded back to 3300' and topped with 5 sx cement.
11/19/2013- Tried to pull casing and only got 2" of stretch in casing and only 500' could be recovered. Perforated at 1450', 820' and 320'. Ran tubing to 1500' and pumped 210 sx cement. Cement circulated out back side. POOH. Hooked to casing and pumped 100 sx cement. Cement circulated out braden head. Closed braden head valve and pressured up to 200 psi and shut in casing.

GPS: 38.63013 -098.61102

Perfs:


Top	Bot	Thru	Comments
3340	3348		

Remarks: COPELAND ACID AND CEMENTING TICKET # 40549

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

KCC WICHITA

NOV 25 2013

✓ 12/20/2013

DEC 04 2013

Form CP-2/3

RECEIVED