

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-03341-00-00
Spot: N2NENE Sec/Twnshp/Rge: 23-16S-12W
330 feet from N Section Line, 660 feet from E Section Line
Lease Name: MINNIE Well #: 1
County: BARTON Total Vertical Depth: 3350 feet

Operator License No.: 9951
Op Name: KRIER, KIRBY OIL, INC.
Address: 1043 NE 80TH RD
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3333		100 SX
SURF	8.62	417		220 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/03/2013 2:30 PM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: KIRBY KRIER Company: KRIER OIL Phone: (620) 562-7637

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement, 15 sx gel and 500 # hulls.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 12/03/2013 6:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perforated at 1500' and 710'. Ran tubing to 3100' and pumped 15 sx gel followed by 50 sx cement w/100 # hulls. Pulled tubing to 1500' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 717'. Cicularated cement to surface with 75 sx cement. Pulled tubing. Topped off with 15 sx cement.

GPS: 38.65135 -098.61045

Perfs:

Top	Bot	Thru	Comments
3333	3350		

Remarks: QUALITY OILWELL CEMENTING

Plugged through: CSG

KCC WICHITA

DEC 09 2013

RECEIVED

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

✓ 12/20/2013

Form CP-2/3

DEC 05 2013