

To: 1 041246
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-22,438-0000
C NW NE, SEC. 13, T 32 S, R 11 W X
4620 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5050
Operator: Hummon Corporation
Name:
Address 950 N. Tyler Rd.
Wichita, KS 67212-3240

Lease Name McGuire A Well # 1
County Barber 148.07
Well Total Depth 4556 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 309

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 5 p.m. Day: 29 Month: 4 Year: 19 97

Plugging proposal received from Manny Boatwright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4554' w/115 sx cement, PBD 4516', Perfs at 4422-24, 4433-41'
1st plug sand back to 4368' and dump 5 sx cement on top of sand through bailer,
2nd plug at 600' with 50 sx cement, 3rd plug at 330' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 6:15 p.m. Day: 29 Month: 4 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4368' and dumped 5 1/2" cement on top of sand
bridge through bailer,

Loaded hole with gel and spotted plugs through 5 1/2" casing:
2nd plug at 600' with 50 sx cement,
3rd plug at 330' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3800' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

DATE MAY 05 1997
WV. NO. 48058

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
MAY 2 1997
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas