

1 010002

API NUMBER 15- 007-21,765 - *CR*

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW SE SW, SEC. 13, T 32 S, R 11 *(W) EX*

990 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5105

Lease Name Rankin Well # 1

Operator: Clarke Corporation

County Barber 122.30

Name & Address P. O. Box 187

Well Total Depth 3763 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 268

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 4:00 pm Day: 8 Month: July Year: 19 85

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 5 1/2" at 3763' PBSD 3734' Perfs at 3609-14

1st plug sand back to 3555' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and pump 125 sx cement.

Plugging Proposal Received by Steve Durrant

(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 5:00 pm Day: 8 Month: July Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 3555 and dumped 5 sx cement on top of sand

through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel,

released 8 5/8" rubber plug and pumped 125 sx cement.

RECEIVED  
MIII 22 1985  
7-22-85  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas

Maximum pressure 750 psi and shut in 500 psi

Remarks: Recovered 2800' 5 1/2" casing. Used 60/40 Pozmix 6% gel by BJ-Titan  
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-85

Signed *Jack H. ...*  
(TECHNICIAN)

INV. NO. 9067