

To: 1 040641
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

3-30 API NUMBER 15-007-21,721-0000 180 R
150' NE of
C NE NW, SEC. 13, T 32 S, R 11 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 30128

Operator: Kenneth S. White
Name & Address 200 E. 1st, Suite 210
Wichita, KS 67202

App. 4695 feet from S section line

App. 3225 feet from E section line

Lease Name Hrencher Well # 1

County Barber 119.66

Well Total Depth 3682 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 216

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 30 Month: 3 Year: 19 92

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 3682' w/100 sx cement, PBD 3627.5', Perfs at 3611-18'

1st plug pump 25 sx cement at 3550',

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:50 a.m. Day: 30 Month: 3 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug pumped down 5 1/2" casing with 50 sx common cement, stopped plug at 3550',

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximim pressure 550 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services. Recovered 3000' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(void if not) observe this plugging.

DATE 4-8-92
34916

Signed Stephen J. Phillips
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
APR 01 1992
CONSERVATION DIVISION
WICHITA, KANSAS