

To: 1 052126
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

4-24 API NUMBER 15-007-21,908-0000
150' SW of
C NW SE, SEC. 12, T 32 S, R 11 W/X
1875 feet from S section line
2085 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5050
Operator: Hummon Corporation
Name:
Address 950 N. Tyler Rd.
Wichita, KS. 67212-3240

Lease Name Ricke Estate Well # 3
County Barber 122.20
Well Total Depth 3760 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 224

Abandoned Oil Well Gas Well Input Well SWD Well O&A
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 467, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 24 Month: 4 Year: 19 97

Plugging proposal received from Manny Boatwright
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 3759' w/100 sx cement, PBTB 3724', Perfs at 3618-22'
1st plug sand back to 3580' and dump 5 sx cement on top of sand through bailer
Spot through 5 1/2" casing:
2nd plug at 600' with 10 sx gel and 50 sx cement,
3rd plug at 250' with 50 sx cement, 4th plug at 40' with 10 sx cement.

1991 APR 29 11:55 AM
4-29-97
RICE VEIL
MAISAS CORP COMM

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:20 a.m. Day: 24 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3580' and dumped 5 sx cement on top of sand through bailer,
Spotted through casing:

2nd plug at 600' with 10 sx gel and 50 sx cement,
3rd plug at 250' with 50 sx cement,
4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2730' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)
I (did / ~~did not~~) observe this plugging.

INVOICED
DATE APR 29 1997
INV NO. 48040

Signed Richard M. Lacey (TECHNICIAN)

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: September 5 1984
month day year

API Number 15-007-21988-0000

150' SW of East
C... NW... SE Sec 12... Twp 32... S, Rge 11... West
(location)

OPERATOR: License # 5050
Name Hummon Corporation
Address 400 One Main Place
City/State/Zip Wichita, KS 67202
Contact Person Wilber Berg
Phone 263-8521

1875... Ft North from Southeast Corner of Section
2085... Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5148
Name Big-H Drilling, Inc.
City/State Wichita, Kansas

Nearest lease or unit boundary line 555... feet.
County Barber
Lease Name Ricke Estate Well# 3

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4000... feet
Projected Formation at TD Lansing
Expected Producing Formations

Depth to Bottom of fresh water 100... feet
Lowest usable water formation Salt Plain Slt
Depth to Bottom of usable water 200... feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 200... feet
Conductor pipe if any required... feet
Ground surface elevation... feet MSL
This Authorization Expires
Approved By

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 8-22-84 Signature of Operator or Agent Kenneth S. White Title Agent

Form C-1 4/84

RECEIVED
KANSAS CORP COMM
1991 APR -2 P 1:33
4-2-97