

1 060203 ○

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-007-21,777 -0000

C SW SW, SEC. 12, T 32 S, R 11 W  
660 feet from ~~W/S~~ section line  
660 feet from ~~W/E~~ section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Ricke "B" Well # 1

Operator: TXO Production Corp.

County Barber

Name & Address 200 West Douglas, Suite 300

Well Total Depth 3730 <sup>121.23</sup> feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 346

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Aldebaran Drilling Co., Inc. License Number 5829

Address Box 18611, Wichita, KS 67207

Company to plug at: Hour: 7:00 am Day: 13 Month: March Year: 19 84

Plugging proposal received from Mark Gwinn

(company name) Aldebaran (phone) 316-685-5372

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug at 713' with 35 sx cement

2nd plug at 372' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement

6th plug to circulate mousehole with 10 sx cement

Plugging Proposal Received by Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 6:45 pm Day: 13 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 713' with 35 sx cement, 2nd plug at 372' with 50  
sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface  
with 10 sx cement, 5th plug to circulate rathole with 10 sx cement, 6th plug to  
circulate mousehole with 10 sx cement.

STATE CORPORATION COMMISSION

Don Ubel gave the orders

MAR 19 1984

3-19-84  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun  
(if additional description is necessary, use BACK of this form.)

INVOICED

(do not) observe this plugging.

Signed Paul A. Luthi  
(TECHNICIAN)

DATE 3-22-84

INV. NO. 0894 3-13