

1040995

8-30

API NUMBER 15- 007-21,689 -00-01

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

C SE SW, SEC. 12, T 32 S, R 11 W/E
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name M-R Well # 1

Operator: Hummon Corporation

County Barber 121.62

Name: 200 W. Douglas, Ste. 1020

Well Total Depth 3742 feet

Address: Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 282

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number 5105

Address: P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 2:30 p.m. Day: 30 Month: 8 Year: 19 95

Plugging proposal received from Alan Vratil

(company name) Clarke Corporation (phone) 316-886-5665

logs: 5 1/2" at 3737' w/300 sx cement, Perfs at 2556-63, 2569-72, 2779-82, 3622-32'

1st plug set CIBP at 2500' and dump 2 sx cement on top,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 p.m. Day: 30 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug set CIBP at 2500' and dumped 2 sx cement on top of CIBP through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs.hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2250' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

SEP 07 1995
9-7-95

CONSERVATION DIVISION
STATE CORPORATION COMMISSION

INVOICED
Observe this plugging.

DATE 9-11-95

INV. NO. 43505

Signed Stephen J. Pfeider (TECHNICIAN)