

To: 1 041243  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

4-22  
API NUMBER 15-007-21,238-00-00  
160' SE of  
SE SW NW, SEC. 35, T 30 S, R 13 W/E  
2770 feet from S section line  
4010 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5506  
Operator: Woolsey Petroleum Corporation  
Name & Address: 107 N. Market, Ste. 600  
Wichita, KS 67202

Lease Name Hartley Well # B-2  
County Barber 128.38  
Well Total Depth 3950 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8 feet 338

Abandoned Oil Well Gas Well  Input Well SWD Well O&A

Other well as hereinafter indicated

Plugging Contractor Clarke Corporation License Number  
Address Medicine Lodge, KS

Company to plug at: Hour: 10:30 a.m. Day: 22 Month: 4 Year: 1997

Plugging proposal received from Alan Vratil  
(company name) Clarke Corporation (phone) 316-886-5665

Work: 4 1/2" at 3949' w/200 sx cement, PBT 3850', Perfs at 3756-60'

1st plug sand back to 3700' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part None

Operations Completed: Hour: 11:30 a.m. Day: 22 Month: 4 Year: 1997

ACTUAL PLUGGING REPORT 1st plug sanded back to 3680' and dumped 4 sx cement on top of sand  
through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,  
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 950 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2500' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 4-28-97

INV. NO. 48019

Signed Stephen J. Pfeifer  
(TECHNICIAN)