

To: 1 010098
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007=21,176 -00-00
C SE SE, SEC. 34, T 30 S, R 13 (W)EX
660 feet from S section line
660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171
Operator: TXO Production Corporation
Name & Address 155 N. Market, Suite 1000
Wichita, KS 67202

Lease Name Hamilton "A" Well # 2
County Barber
Well Total Depth 3920 127.40 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor TXO Production Corporation License Number 5171
Address 155 N. Market, Suite 1000, Wichita, KS 67202

Company to plug at: Hour: 9:30 am Day: 28 Month: February Year: 19 86

Plugging proposal received from Allen Dick
(company name) TXO (phone) 316-269-7600

were: 2 7/8" at 3885' PBD 3810' Perfs at 3740-44'
1st plug pump 10 sx cement to 3650' - shut in
2nd plug perforate at 360' and pump 150 sx cement

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 am Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug pumped 10 sx cement to bottom pushing plug to 3650',
Shut in at 500#, 2nd plug perforated at 360' and pumped 150 sx cement to surface.

Maximum pressure 700 psi and shut in 0

Remarks: Used 60/40 Pozmix by BJ-Titan. No recovery
(If additional description is necessary, use BACK of this form.)

INVOICED
(date of invoice) MAR 12 1986 observe this plugging.
STATE CORPORATION COMMISSION

Signed [Signature]
(TECHNICIAN)

MAR 11 1986

DATE MAR 12 1986
INV. NO. 12969 APR 10 1986
2-28 CONSERVATION DIVISION
Wichita, Kansas