

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- - N/A
SEC. 34, T 30S, R 13 W R
1980 FEET FROM N SECTION LINE
660 FEET FROM W SECTION LINE

TECHNICIAN'S PLUGGING REPORT

OPERATOR LICENSE # 5171

LEASE NAME Hamilton WELL # A #1 OWWO

OPERATOR: TXO Production Corporation
NAME & ADDRESS: 200 W. Douglas
Wichita, Kansas 67202

COUNTY Barber
WELL TOTAL DEPTH 4110 \$133.58 FEET
CONDUCTOR PIPE: SIZE _____ FEET _____
SURFACE CASING: SIZE 8 5/8 FEET 344

ABANDONED OIL WELL GAS WELL INPUT WELL _____ SWD WELL _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR Clark Corporation LICENSE NUMBER 5105

ADDRESS 107 W. Fowler Medicine Lodge 67104

COMPANY TO PLUG AT: HOUR: 10:30am DAY: 25 MONTH: May YEAR: 1983

PLUGGING PROPOSAL RECEIVED FROM Elmo Morgenstern

(COMPANY NAME) Clark Corporation (PHONE) _____

WERE: To use 60/40 pozmix 2% gel 3% cc
1st plug @ 3500 with 20sx cement Squeeze
down 8 5/8" surface pipe with 2sx hulls - 10gel
50sx cement 5 gel - release wipe plug - 100sx cement

PLUGGING PROPOSAL RECEIVED BY Richard W. Lacy
(TECHNICIAN)

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ PART _____ NONE

OPERATIONS COMPLETED: HOUR: 12:15pm DAY: 25 MONTH: May YEAR: 1983

ACTUAL PLUGGING REPORT Plugged as proposed in above
paragraph

500psi Maximum pump pressure
300psi shot in pressure
Recovered 2110' of 2 7/8" production string

REMARKS: Late because company never called in

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1983

CONSERVATION DIVISION
Wichita, Kansas

I (~~DID~~ / DID NOT) OBSERVE THIS PLUGGING.

SIGNED Richard W. Lacy
(TECHNICIAN)

INVOICED

DATE 7-6-83
INV. NO. 4709-W