

To: 1 040645 4-10
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-22,387-00-00 7/R
100' E & 20' S
NE NE, SEC. 32, T. 30 S, R. 13 W X
4600 feet from S section line
560 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030

Lease Name Thompson-Dickinson Well # 1

Operator: Vess Oil Corporation

County Barber

Name & Address 8100 E. 22nd St. N, Bldg. 300

Well Total Depth 4830 156.97 feet

Wichita, KS 67226

Conductor Pipe: Size _____ feet

Surface Casing: Size 10 3/4 feet 295

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1:15 p.m. Day: 10 Month: 4 Year: 19 92

Plugging proposal received from Manny Boatwright

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4726' w/160 sx cement, Perfs at 4612-22'

1st plug sand back to 4560' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release

10 3/4" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:45 p.m. Day: 10 Month: 4 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4555' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 10 3/4" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx
gel, 100 lbs. hulls, and 150 sx cement.

Maximum pressure 400 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3818' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
(If applicable) observe this plugging.

DATE 4-28-92

INV. NO. 35096

Signed Stephen J. Puffer
(TECHNICIAN)

STATE CORPORATION COMMISSION
RECEIVED
APR 14 1992
CONSERVATION DIVISION
Wichita, Kansas