

1080117

R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007- 21,778-00-00

C SW NE , Sec. 2 , T 31 S, R 12 W/E

1980 feet from N/S section line

1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Mott-Amber CreeWell # 1

Operator: Mustang Drilling & Exploration, Inc.  
Name & 200 West Douglas, Suite 800  
Address Wichita, KS 67202

County Barber

Well Total Depth 4328 feet 140.66

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Mustang Drilling & Exploration License Number 5652

Address P. O. Drawer 1609, Great Bend, KS 67530

Company to plug at: Hour: 5:00 am Day: 13 Month: March Year: 1984

VERBAL PLUGGING ORDERS GIVEN TO Gib Overby

(company name) Mustang (phone) 316-267-8011

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1040' with 50 sx cement

2nd plug at 390' with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 10 sx cement

Signed J. H. M. D. (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:00 am Day: 13 Month: March Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1040' with 50 sx cement, 2nd plug at 390' with  
50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to  
surface with 10 sx cement, 5th plug to circulate rathole with 10 sx cement

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun

I hereby certify that the above plugging instructions were given as herein stated  
and that I (did / did not) observe this plugging.

INVOICED

RECEIVED  
STATE CORPORATION COMMISSION

Signed J. H. M. D. (TECHNICIAN)

MAR 23 1984

FORM CP-2/3  
Rev. 9-82

DATE 3-27-84

CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 0956

3-13