

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,747-00-00

C NW SW, Sec. 3, T 31 S, R 12 W/E

1980 feet from N/S section line

660 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

~~5801~~ #5601

Operator License # Assoc. Petroleum Consultants License Name Haas Estate Well # 40

Operator: Suite 600 - One Main Place
Name & Wichita, KS 67202
Address

County Barber

Well Total Depth 4610 feet 149.82

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 349

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Heartland Drilling, Inc. License Number 5867

Address Suite 600 - One Main Place, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 20 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Tharp

(company name) Heartland Drilling (phone) 316-265-9385

were: to fill hole with heavy mud. Spot plugs through drill pipe. first plug at 720' with 50 sx cement, 2nd plug at 390' with 40 sx cement, 3rd plug - solid bridge with 1 sack hulls and 8 5/8" plug. 5th plug - 10 sx cement to surface. Circulate 15 sx cement in the rathole and 10 sx cement in the mousehole.

Signed R. Barlett (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 9:10 am Day: 20 Month: January Year: 19 84

ACTUAL PLUGGING REPORT to fill hole with heavy mud. Spot plugs through drill pipe. 1st plug at 720' with 50 sx cement, 2nd plug at 390' with 40 sc cement. 3rd plug - solid bridge with 1sx hulls and 8 5/8 plug. 5th plug - 10 sx cement to surface. Circulate 15 sx cement in the rathole and 10 sx cement in the mousehole.

Remarks: Sun Cementing completed the cementing with 60/40 Poz with 2% gel and 3% cc. Ticket number 17990.

I hereby certify that the above plugging instructions were given as herein stated and that I ~~xxx~~ / did not) observe this plugging.

Signed R. Barlett (TECHNICIAN)

INVOICED RECEIVED STATE CORPORATION COMMISSION

DATE 1-25-84 JAN 23 1984

V. NO. 9243-4 CONSERVATION DIVISION Wichita, Kansas

1-20