

1 040147

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,808-00-00

C NE NW, SEC. 3, T 31 S, R 12 W/E
660 feet from N/S section line
1980 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name Haas Well # 4

Operator: Bowers Drilling Co., Inc.

County Barber

Name & Address 125 North Market

Well Total Depth 4550 ^{147.88} feet

Address Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KSB Building, Wichita, KS 67202

Company to plug at: Hour: 2:00 am Day: 14 Month: May Year: 19 84

Plugging proposal received from Mike Brentz

(company name) Red Tiger (phone) 316-862-5952

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 660' with 50 sx cement

2nd plug at 270' with 50 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by _____
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 4:45 am Day: 14 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 660' with 50 sx cement, 2nd plug at 270' with
50 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface
with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement

RECEIVED
STATE CORPORATION COMMISSION

MAY 17 1984

CONSERVATION DIVISION
Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun # 18148

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-21-84

Signed [Signature]
(TECHNICIAN)

INV. NO. 15666

5-14