

1 090171

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION 100' W NE SW NW SEC. 3, T 31 S, R 12 W/E
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,822-00-00 R
1650 feet from N/SX section line
890 feet from W/EX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5435

Lease Name Haas Well # 5

Operator: Bowers Drilling Co., Inc.

County Barber

Name & Address 125 North Market

Well Total Depth 4536 147.42 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 221

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Red Tiger Drilling Company License Number 5302

Address 1720 KSB Building, Wichita, KS 67202

Company to plug at: Hour: 3:00 am Day: 25 Month: May Year: 19 84

Plugging proposal received from Randy Knott

(company name) Red Tiger (phone) 316-263-2371

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 630' with 50 sx cement

2nd plug at 270' with 40 sx cement
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

Plugging Proposal Received by R. Bearlutton
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:15 am Day: 25 Month: May Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 630' with 50 sx cement, 2nd plug at 270' with 40 sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

JUN 01 1984

Remarks: Use 60/40 Pozmix 2% gel 3% cc by Sun. # 18954
(if additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 6-5-84

Signed R. Bearlutton
(TECHNICIAN)

INV. NO. 1837
5-25