

1 040528

3-13

203 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 19- 007-22,356-00-00  
NE SW NW, SEC. 8, T. 31 S, R. 12 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 30217

Operator: Robba Exploration, Inc.

Name & Address: 230 N. Market

Wichita, KS 67202

3630 feet from S section line

4290 feet from E section line

Lease Name Gress Well # 6

County Barber 147.25

Well Total Depth 4531 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Company License Number 5418

Address P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: 12:30 a.m. Day: 13 Month: 3 Year: 19 91

Plugging proposal received from Vince Schrappe

(company name) Allen Drilling Company (phone) 316-793-5681

Remarks: to fill hole with heavy mud and spot cement through drill pipe Elevation 1720' Anhydrite 670'

1st plug at 660' with 100 sx cement,

2nd plug at 290' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 6:45 a.m. Day: 13 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 660' with 100 sx cement,

2nd plug at 290' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 20 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(if additional description is necessary, use BACK of this form.)

(if not) observe this plugging.

INVOICED

DATE 4-3-91

INV. NO. 31308

3-13

RECEIVED STATE CORPORATION COMMISSION

MAR 15 1991

CONSERVATION DIVISION Wichita, Kansas

Signed Stephen J. Pfeifer (TECHNICIAN)