

15-007-00673-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
4-16-82
APR 16 1982

WELL PLUGGING RECORD

Give All Information Completely
Make Required

CONSERVATION DIVISION
Wichita, Kansas

COUNTY Barber SEC. 18 TWP. 32S RGE. 11W E/W
Location as in quarters or footage from lines:

C SW/4 SE/4

Lease Owner Phillips Petroleum Company

Lease Name Gilbert AB-1 Well No. _____

Office Address Box 287 Great Bend, Kansas 67530

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 4-1-82

Plugging completed 4-6-82

Reason for abandonment of well or producing formation
Depleted

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 4340'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	209'	none
				4-1/2"	3639'	3299'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom was plugged off with sand to 3347' and 4 sacks cement ran. Shot casing @3428' and 3322'. Pulled a total of 104 joints of pipe. Plugged well with 6 sacks hulls, 25 sacks gel, 150 sacks 50/50 common cement, 2% gel, 3% cc.
Plugging Complete.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 176 Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 12th day of April, 1982

Irene Hoover
Notary Public.

My Commission expires:

