

15-007-00673-0000

cc: R. E. Dowden-OK City
B. A. Conner-357 FPB
File

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
APR 14 1982

APR 14 1982
4-14-82
CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barber SEC. 18 TWP. 32S RGE. 11 N/W
Location as in quarters or footage from lines:
C SW/4 SE/4

Locate Well
correctly on above
Section Platt.

Lease Owner Phillips Petroleum Company
Lease Name Gilbert "AB" Well No. 1
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 08-27-64
Application for plugging filed 01-11-82
Plugging commenced 03-25-82
Plugging completed 04-07-82
Reason for abandonment of well or producing formation Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation Douglas Depth to top 3568' bottom 3574' T.D. 3606'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Surface	water	0	209'	8 5/8"	209'	-0-
Production	gas & water	0	3639'	4 1/2"	3640'	33299'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. On 03-25-82 contact State Plugging Agent. MIRU Pratt Well Service & pulled & LD R&T. Dumped 10 sx sand (1000#) down 4 1/2" csg. Fill up to 3347'. Dump bail 4 sx cement on top of sand. RDMO Pratt Well Service. On 04-02-82, MIRU Kelso Csg Pullers. Pulled 26" stretch on 4 1/2" csg. Shot csg @ 3328' - not loose. Shot @ 3300' and csg came loose. LD 30 jts 4 1/2" csg. Pulled & LD 74 jts 4 1/2" csg (total 104 jts). Installed plug container in 8 5/8" csg. On 04-07-82, MIRU Sun Cementing to 8 5/8" csg. Pumped 15 sx gel, 6 sx hulls, 10 sx gel, wiper plug & 150 sx common cement w/3% CaCl. Max press-700#. ISIP-400#. RDMO Sun Cementing. To cut off & weld plate on 8 5/8" csg. Well P & A, 04-07-82.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company

STATE OF KANSAS COUNTY OF BARTON, ss.

C. D. Dohrer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. D. Dohrer Area Manager
Box 287, Great Bend, KS 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of April, 1982

Velma L. Mog
Velma L. Mog Notary Public.

My Commission expires: February 15, 1984

