


15-007-00097-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 17 Twp 32 Rge. K 11 (E) W (W)
Location as "NE/CNW/SW" or footage from lines C SW NW
Lease Owner Mill Drilling Co. Inc.
Lease Name Peace Treaty Association Well No. 1
Office Address 670 N. 4th. Natl. Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 6-3-62 19
Application for plugging filed 6-3-62 19
Application for plugging approved 6-3-62 19
Plugging commenced 10:30 P.M. 6-3-62 19
Plugging completed 11:30 P.M. 6-3-62 19
Reason for abandonment of well or producing formation Non Productive.
If a producing well is abandoned, date of last production _____ 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation Dry in Simpson Depth to top _____ Bottom _____ Total Depth of Well 4713 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole filled with drilling mud to within 240' of surface, with a plug put at this depth. 1/2 sack hulls put on top of plug and 20 sacks cement added. Hole then filled to within 40' of surface and a plug put at this depth with 1/2 sack hulls put on plug and 10 sacks cement was then added, this filled hole to surface. Two sacks cement was put in rat hole bridging same. This completed plugging.

RECEIVED
STATE CORPORATION COMMISSION
JUN 11 1962
6-11-62
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Co. tools.
Address Same as above.

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Joseph O. Butts (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joseph O. Butts
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 5th day of June, 19 62

Bettis H. Salter
Notary Public.

My commission expires October 16, 1965

INVOICED
DATE 6/11/62
INV. NO. 5148-W

ROTARY DRILLERS LOG

COMPANY: Mull Drilling Co., Inc. et al ROTARY DRILLING COMMENCED: 5-21-62
 Wichita, Kansas

CONTRACTOR: Mull Drilling Co., Inc. ROTARY DRILLING COMPLETED: 6- 2-62
 Wichita, Kansas

CASING RECORD: Set 250' of 8-5/8" casing LOCATION: PEACE TREATY #1
 with 175 sacks quickset C SW NW 17-329-11W
 cement. D & A Barber County, Kansas

(Figures indicate bottom of formation - measurements from top of Rotary Bushing)

855'	Red bed & shale
1475'	Shale w/ shells
1700'	Shale & lime
2265'	Lime & shale
3079'	Shale & lime
3643'	Sandy lime & shale
4174'	Lime w/ shale
4225'	Lime
4347'	Lime w/ shale
4395'	Misc.
4415'	Misc. chert
4482'	Misc. lime
4510'	Lime & shale
4612'	Kinderhook shale
4690'	Viola lime
4713'	Simpson sand - Total Depth

RECEIVED
 STATE CORPORATION COMMISSION
 JUN. 11 1962
 6-11-62
 CONSERVATION DIVISION
 Wichita, Kansas

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.


MULL DRILLING COMPANY, INC.

 Delbert J. Costa, Geologist

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 7th day of June, 1962.




 Mudge N. Miller Notary Public

Witnesses: February 24, 1964