

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas.

WELL PLUGGING RECORD

NORTH

		0	
	SECTION 27		

Locate well correctly on above
Section Plat

BARBER County. Sec. 27 Twp. 34S Rge. 13W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SW NE
Lease Owner PETROLEUM, INC.
Lease Name BLUNK UNIT Well No. 1
Office Address ROUTE 2, GREAT BEND, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed SEPTEMBER 14 19 59
Application for plugging filed SEPTEMBER 14 19 59
Application for plugging approved SEPTEMBER 14 19 59
Plugging commenced SEPTEMBER 14 19 59
Plugging completed SEPTEMBER 14 19 59
Reason for abandonment of well or producing formation NO PRODUCIBLE ZONES

If a producing well is abandoned, date of last production ----- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well W. L. LACKAMP, STAFFORD, KANSAS
Producing formation ----- Depth to top ----- Bottom ----- Total Depth of Well 3685 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	286'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ----- feet to ----- feet for each plug set.

MUD UP WITH HEAVY MUD TO 275' FOLLOWED BY A WOODEN PLUG AND 1/3 SACK HULLS.
PLACED 20 SACKS CEMENT THROUGH DRILL PIPE ON TOP OF PLUG. MUD UP TO 35'
FOLLOWED BY A WOODEN PLUG AND 1/3 SACK HULLS. FILLED HOLE TO BASE OF WELL
CELLAR WITH 10 SACKS OF CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE 2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
DON SEARLE (employee of owner) or () of the above-described
well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the
above-described well as filed and that the same are true and correct. So help me God.

(Signature)

ROUTE 2, GREAT BEND, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 30TH day of SEPTEMBER, 19 59

My commission expires APRIL 14, 1963

Notary Public

WELL LOG

COMPANY Petroleum, Incorporated

SEC. 27 T-34S R. 13W

FARM BLUNK UNIT NO. 1


LOC. C-SW, NE

TOTAL DEPTH 3685'

COUNTY BARBER CO., KANSAS

COMM. September 7, 1959 COMP. September 14, 1959

CONTRACTOR GARVEY DRILLING COMPANY



CASING 8 5/8" @ 286' W/175 sax.

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

135	Red bed & surface sand
875	Red bed
1145	Shale
1350	Shale & shells
1825	Shale & lime
2135	Lime
2450	Lime & shale
2545	Shale & lime
2775	Lime & shale
3010	Shale & shells
3255	Lime & shale
3580	Shale & lime
3682	Shale
3685	Sand
3685	T. D.

RECEIVED
STATE CORPORATION COMMISSION
OCT 2 1959
CONSERVATION DIVISION
Wichita, Kansas

State of KANSAS }
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 BLUNK UNIT well.

Verne A. Morris

Subscribed and sworn to before me this 30th day of September 19 59

My Commission Expires: April 14, 1963

Arthur J. Wiles
NOTARY PUBLIC