

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division,  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 29 Twp. 34 Rge. 13 (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW NW  
Lease Owner H.C. Bennett  
Lease Name Roberts Well No. 1  
Office Address 1212 Union Nat'l Bldg. Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) gas well  
Date well completed 12-16-64 19  
Application for plugging filed 8-30-68 19  
Application for plugging approved 9-3-68 19  
Plugging commenced 9-5-68 19  
Plugging completed 9-10-68 19  
Reason for abandonment of well or producing formation depleted

NORTH

X			

Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren  
Producing formation Depth to top Bottom Total Depth of Well 4881 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	485'	none
				5 1/2	4881'	3865'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Globe Cementing Co. pumped 20 sacks of cement down 5 1/2" pipe

Set 20' rock bridge from 300' to 280' and dumped 25 sacks of cement

Mud hole to 40' and rock from 40' to 30' and dump 10 sacks of cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 3 - 1968  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Flint Engineering and Const. Co.  
Address 2375 W. Central El Dorado, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) *R. M. Smith*

(Address)

Subscribed and sworn to before me this 24 day of Sept., 1968

Sept. 19, 1971

*James J. Davis*  
Notary Public.



WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas


COPY

Company. SKELLY OIL COMPANY  
Farm. Jacob Roberts No. 1

SEC. 29 T. 34 R. 13W  
NE NW NW  
330' from NL, 990' from WL  
of NW/4  
County Barber

Total Depth. 4881'  
Comm. 9-25-64 Comp. 12-16-64  
Shot or Treated. MISSISSIPPIAN 4840' 68 shots  
Contractor. K & E Drlg.  
Issued. 3-6-65

KANSAS



Elevation. 1712' KB

Production. 2090 MCFGPD

CASING:

8 5/8" 485' cem w/300 sx  
5 1/2" 4881' cem w/100 sx

Figures Indicate Bottom of Formations.

Clay and sand	50
red bed	135
shale and sand	197
shale and shells	1000
shale	1045
shale and shells	1930
lime	2095
lime and shale	2300
lime	3010
lime and shale	3890
lime	4816
cherty dolomite	4855
lime	4881
Total Depth	4881

TOPS: LOG

Heebner	4031
Lansing	4202
Base Kansas City	4708
Mississippian	4816

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 3 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Ran Wellex Forxo Log, Acoustic Velocity Log & Gamma-Guard Log from 4881' to surface.