

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,296-0000

LEASE NAME Sterling

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

3630 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 34 TWP. 34 SRGE. 13 (N) or (W)

COUNTY Barber

LEASE OPERATOR Blackhawk Exploration, Inc.

ADDRESS 200 E. First, #100, Wichita, KS 67202

PHONE# (316) 265-6431 OPERATORS LICENSE NO. 4480

Date Well Completed 5-1-90

Character of Well D & A

Plugging Commenced 5-6-90

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 5-6-90

The plugging proposal was approved on 5-6-90 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. _____

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	324.12	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
Fill hole w/heavy mud, 1st plug at 900' to 700' w/50 sx; 2nd plug at 310' to 110' w/50 sx; 3rd plug at 40' to surface w/10 sx; 15 sx in rathole, 10 sx in mousehole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Abercrombie Drilling, Inc. License No. 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Blackhawk Exploration, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Jack K. Wharton

(Signature) Jack K. Wharton

(Address) 150 N. Main, Suite 801
Wichita, KS 67202

SUBSCRIBED AND SWORN TO before me this 20th day of June, 19 90



RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1990
CONSERVATION DIVISION
Wichita, Kansas
Commission Expires: 8/15/92

Susan M. Williams
Notary Public

ABERCROMBIE DRILLING, INC.

801 UNION CENTER
WICHITA, KANSAS 67202

DRILLER'S WELL LOG

Blackhawk Exploration, Inc.
Sterling #1
S/2 N/2 NE
Sec. 34-34S-13W
Barber County, Kansas

05-01-90	0 to 96	Redbed
	96 to 329	Redbed and Sand
05-02-90	329 to 945	Shale and Redbed
	945 to 1495	Shale
05-03-90	1495 to 1724	Shale and Lime
	1724 to 1730	Anhydrite
	1730 to 2495	Lime and Shale
05-04-90	2495 to 3185	Lime and Shale
05-05-90	3185 to 3625	Lime and Shale
05-06-90	3625 to 3675	Lime and Shale
	3675	Rotary Total Depth

RECEIVED
STATE CORPORATION
JUN 21 1990
CONSULTING ENGINEER
Wichita, Kansas