


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Barber County, Sec. 4 Twp. 30 Rge. 13 E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
C SE NW

Lease Owner Cities Service Company  
Lease Name Lambert "A" Well No. 2  
Office Address 700 Sutton Place Bldg. Wichita, KS 67202  
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plot

Date Well completed 19  
Application for plugging filed Verbal - 7-5 1977  
Application for plugging approved Verbal - 7-5 1977  
Plugging commenced 7-5 1977  
Plugging completed 7-5 1977  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well  
Producing formation Depth to top Bottom Total Depth of Well 4770'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	326'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 350'. Spot 35 sacks HOWCO Lite to 235'. Mud from 235' to 40'.  
Plug and 1/2 sack hulls at 40'. 12 sacks cement HOWCO Lite to bottom of cellar. 3 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 20 1977

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Gabbert - Jones Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.  
W. J. Devaney (employee of owner) or (owner or operator)  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. J. Devaney*

SUBSCRIBED AND SWORN TO before me this 28<sup>TH</sup> day of July, 1977

*Glenn E. Meier*  
Glenn E. Meier Notary Public.

My commission expires 6-3-81

GABBERT-JONES, INC.  
 WICHITA, KANSAS  
 DRILLERS' WELL LOG

Lambert A#2  
 Sec 4-308-13W  
 Barber County Kansas

Commenced: 6-20-77

Completed: 7-5-77

OPERATOR: CITIES SERVICE OIL CO.

Depth		Formation	Remarks
From	to		
0	205	Sand	Ran 7 jts of 24# 8 5/8" csg set @ 326' Cemented w/325 lbs 50/50 Posmix 2% CC PD @ 2:20 p.m. 6-21-77
205	820	Redbed-Shale	
820	1100	Shale	
1100	2015	Shale-Shells	
2015	2218	Lime-Shale	
2218	2425	Shale-Lime	
2425	2790	Lime-Shale	
2790	3280	Lime	DRY & ABANDONED
3280	3335	Lime-Shale	
3335	3535	Lime	
3535	3920	Lime-Shale	
3920	4765	Lime	
	4765 - TD		

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above  
 Drillers' Well Log is true and correct to the best of my knowledge and belief and  
 according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
 JAMES S. SUTTON II

Subscribed and sworn to before me this 14th day of July, 1977.

*Elizabeth J. Edwards*  
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1979.

