

15-007-00182-0000

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JAN 23 1964
1-23-64
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name H. C. Bennett

Complete Address: 1212 Union National Bldg., Wichita, Kansas

Lease Name Stewart Well No. # C-1

Location SW SW SW Sec. 14 Twp. 32 Rge. 11 (E) (W) W

County Barber Total Depth 3587

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Flint Engineering & Construction Co.

Address: Box 342, El Dorado, Kansas License No. 547

Operation Completed: Hour 1:30PM Day 20th Month Jan. Year 1964

The Above well was plugged as follows:

183' of 8 5/8" surface pipe, cemented with 120 sacks. 3567' of 5 1/2" long
string, cemented with 75 sacks. Bottom of hole was sanded to 3560', and
cemented with 5 sacks. Pipe was shot off at 3200', and 16 joints were
pulled and the Gas blew. 200 sacks cement, 65 sacks Gel, 15 sacks hulls,
11 sacks Flo Seal, and 250 sacks weight mud was pumped in hole to kill
Gas, and finally it was killed with water, this was done by Globe Cement-
ing Co. Due to gas it was necessary to squeeze. 15 sacks Gel Mud and 80
sacks cement was pumped into surface pipe, through a swage, to a pressure
of 400 lbs. This was done by Halliburton Cementing Co. 3200' of 5 1/2" long
long string was recovered from the hole.
I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Archie Elving
Well Plugging Supervisor

DATE 1/22/64

INV. NO. 8498-u

30
16
15
30
9
9.5.0