

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 3 1962
7-3-62
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Jones-Gebert Oil Inc.

Complete Address: 1007 Central Building Wichita, 2 Kansas.

Lease Name Kiras Well No. I.

Location NW-NW-SE 2 30S 14W Sec. 2 Twp. 30 Rge. 30S (E) (W14)

County Barber Total Depth 1405 ft.

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Plugging Contractor: Jones-Gebert Oil Inc.,

Address: 1007 Central Building Wichita, Kansas. License No.

Operation Completed: Hour 12:30 pm Day 30 Month June Year 1962

The Above well was plugged as follows:

320# 8 5/8" surface pipe. Surface pipe circulated with cement. Hole
filled with heavy drilling mud to 286'. 1/2 sack hulls and first
cementing plug, 20 sacks cement. Filled to 40' with heavy drilling mud,
1/2 sack hulls and second cementing plug. 10 sacks cement to bottom of
cellar. Bridge and 2 sacks cement in rathole.

(NOTE) Circulation was lost at 900' in first attempt. Hole was
plugged as described above. Rig skidded 12' west of original location.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/2/62
INV. NO. 5299-w

Signed: Herman Justus
Well Plugging Supervisor