

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

APR 1 1963

4-1-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Stelbar Oil Corporation Inc.

Complete Address: 310 Petroleum Bldg., Wichita, Kansas

Lease Name Kiras Well No. # 1

Location SW SW NE Sec. 2 Twp. 30 Rge. 14 (E) (W) W

County Barber Total Depth 4553

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Glen & Smith Pipe Pulling

Address: 204 East 6th, Ellinwood, Kansas License No. 396

Operation Completed: Hour 12 Noon Day 25th Month March Year 1963

The Above well was plugged as follows:

322' of 8 5/8" surface pipe circulated with cement. 4547' of 5 1/2" long
string cemented with 100 sacks. Plugged back to 4470'. Top perforation
4425'. Sanded to 4415' cemented with 5 sacks. Hole was filled to 200'
10' rock bridge cemented with 20 sacks. Hole filled to 40' with mud
10' rock bridge cemented with 10 sacks to base cellar.
3936' of 5 1/2" pipe recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Arlene Elving
Well Plugging Supervisor

DATE 4/1/63

INV. NO. 6796-W