

DISTRICT CONSERVATION AGENT'S REPORT

*CPB*  
*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 39-13

LOCATION NW-SE-7E

SEC. 2 TWP. 30 RGE. 14-W

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 2 Lease Clara Allen

Operator Mr. H.V. Cluwell Address 611 N. 1st Bldg. Wichita-Kans.

Field \_\_\_\_\_ County Barber

Total Depth 4578 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/8 - 475 ft. Circulated with cement  
5 1/2 casing set at 4552 ft. - Cemented with 250 sacks cement.  
Barber Plug at 3840 ft. - filled with chat to 3810 ft. -  
Dumped 4 sacks of cement at 3510 ft. - Filled with mud  
& 275 ft. - Ripped off & pulled the 5 1/2 casing - Set back  
bridge & 15 sacks of cement at 275 ft. Filled to 30 ft. -  
Plug & 10 sacks of cement at the surface.  
A. & S. Pipe Pulling Co. - Plugging

**RECEIVED**  
STATE CORPORATION COMMISSION

DEC 13 1950  
12-13-50  
CONSERVATION DIVISION  
Wichita, Kansas

C. D. Stough  
District Conservation Agent

Date 12-10-50

**PLUGGING**  
FILE SEC 2 T 30 R 14 W  
BOOK PAGE 39 LINE 25