

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-21951-00-00

LEASE NAME Mott

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 17

660 Ft. from S Section Line

4520 Ft. from E Section Line

LEASE OPERATOR Gore Oil Company

SEC. 1 TWP. 31S RGE. 12 ~~XXXX~~ (W)

ADDRESS P.O. Box 2757, Wichita, KS 67201-2757

COUNTY Barber

PHONE#(316 263-3535 OPERATORS LICENSE NO. 5552

Date Well Completed _____

Character of Well Good

Plugging Commenced 1-19-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 1-22-98

The plugging proposal was approved on 1-19-98 (date)

by Steve Piefer (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation Miss Depth to Top 4246 Bottom 4257 T.D. 4330

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	344	None
				4 1/2	4329	3200

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Lay down rods, tubing and casing swab oil out of hole, sand well back to 4175, pump 4sx portland cement with dump bailer, stretch and cut pipe at 3200, lay down casing, Allied pump 300 hulls, 10 jel, 50sx cement, 8 jel, 100 hulls, 8 5/8 wiper plug and 100sx, 60/40 6% jel

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Clarke Corporation License No. 5105

Address P.O. Box 187, Medicine Lodge, KS 67104


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Gore Oil Company

STATE OF Kansas COUNTY OF Barber, ss.

Alan Vratil (Employee of Operator) or (Operator)
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact
statements, and matters herein contained and the log of the above-described well as filed th
the same are true and correct, so help me God.

(Signature) [Signature]

(Address) Medicine Lodge, KS 67104/VED



STATE CORPORATION COMMISSION
SUBSCRIBED AND SWORN TO before me this 27 day of January, 1998

[Signature] Glenda Morrison
Notary Public

My Commission Expires: 10/14/98

CONSERVATION DIVISION
Wichita, Kansas