


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas 67202

NORTH



Locate well correctly on above
Section Plat

Barber County, Sec. 4 Twp. 31S Rge. 12W (W) (W)
Location as "NE/CNW/SW" or footage from lines C. SE NW
Lease Owner Kathol Petroleum, Inc.
Lease Name Olson 'A' Well No. 1
Office Address 900 Sutton Place, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 23, 1970
Application for plugging filed January 7, 1971
Application for plugging approved December 28, 1970
Plugging commenced December 23, 1970
Plugging completed December 23, 1970
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. Russell Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3800 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	267'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.


Filled hole with heavy cut mud to 260'
1/2 sack hulls & plug at 260' w/35 sacks cement
Filled hole with heavy cut mud to 40'
1/2 sack hulls & plug at 40' w/10 sacks cement
2 sacks cement in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1971
CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor Kathol Petroleum, Inc.
Address 900 Sutton Place, Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Homer J. Catt (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Homer J. Catt
900 Sutton Place, Wichita, Kansas
(Address)



Subscribed and sworn to before me this 7th day of January, 1971

My commission expires June 19, 1972
Katherine A. Stitt Notary Public.

DRILLERS LOG

#1 OLSON 'A'

CASING RECORD:	OPERATOR:	Kathol Petroleum, Inc.	DESCRIPTION:
8-5/8" @ 267' w/ 220 sacks cem.	CONTRACTOR:	Kathol Petroleum, Inc.	50' E. of C. SE NW Sec. 4-31S-12W Barber County, Kansas
	COMMENCED:	December 16, 1970	ELEVATION: 1720' K.B.
	COMPLETED:	December 23, 1970	I.P. Dry & Abandoned
TOTAL DEPTH: 3800'			

<u>FORMATION:</u>	<u>FROM:</u>	<u>TO:</u>	<u>REMARKS:</u>
surface hole	0	270	
red bed	270	950	
shale & shells	950	1661	
anhydrite	1661	1673	
shale & lime	1673	1682	
shale & lime	1682	1900	
lime	1900	2112	
lime & shale	2112	2365	
lime & shale	2365	2470	
shale & lime	2470	2745	
lime & shale	2745	2990	
shale & lime	2990	3140	
shale	3140	3195	
lime & shale	3195	3355	
lime & shale	3355	3503	
lime & shale	3503	3657	
lime & shale	3657	3668	
shale & sand	3668	3696	
shale & sand	3696	3765	
shale & sand	3765	3800 R.T.D.	

RECEIVED
STATE CORPORATION COMMISSION
JAN 8 1971
CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above information is true and correct to the best of my knowledge.

KATHOL PETROLEUM, INC.

Jack P. Keane
Jack L. Keane, Vice President

Subscribed and sworn to before me this 6th day of January, 1971.

KATHERINE A. STITT
Katherine A. Stitt Notary Public

