

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-007-22,211-00-00

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1988

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE NAME HAAS

WELL NUMBER 10

4620 Ft. from S Section Line

165 Ft. from E Section Line

SEC. 4 TWP. 31 RGE. 12 ~~06~~ or (W)

COUNTY Barber

Date Well Completed 11-07-88

Plugging Commenced 11-08-88

Plugging Completed 11-08-88

LEASE OPERATOR CONSERVATION DIVISION  
Wichita, Kansas Drilling Company, Inc.

ADDRESS 125 North Market, Suite 1425 Wichita, KS 67202

PHONE# (316) 262-6449 OPERATORS LICENSE NO. 5435

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 11-04-88 (date)

by Steve Durant (KCC District Agent's Name).

Is ACO-1 filed? to be filed  
by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4500'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

Bottom Plug: @500' w/50 sacks cement thru drill pipe

Next Plug: @ 300' w/40 " " " " "

Top Plug: @40' w/10 sacks cement

15 sacks cement in Rat Hole

(if additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Duke Drilling Co., Inc. License No. 5929

Address P.O. Box 823 Great Bend, KS 67530

STATE OF Kansas COUNTY OF Barton, ss.


Leonard Williamson (Employee of Operator) or ~~XXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Leonard Williamson

(Address) P.O. Box 823 Great Bend, KS 67530

SUBSCRIBED AND SWORN TO before me this 11<sup>th</sup> day of November, 1988

K. Rodney M. Hague  
Notary Public



Commission Expires: 5-5-90

DRILLER'S WELL LOG

DATE COMMENCED: October 31, 1988  
DATE COMPLETED: November 8, 1988

Bowers Drilling Company, Inc.  
HASS #10  
E/2 E/2 NE NE  
Sec. 4, T31S, R12W  
Barber County, Ks.

ELEVATION: 1725 K.B.

0 - 291' Surface Soil, Red Clay, Shale  
291 - 885' Red Bed  
885 - 1446' Shale  
1446 - 1905' Shale & Lime  
1905 - 3591' Lime & Shale  
3591 - 3596' Shale  
3596 - 3625' Lime & Shale  
3625 - 3791' Shale  
3791 - 4217' Lime  
4217 - 4297' Shale & Lime  
4297 - 4472' Chert & Lime  
4472 - 4500' Chert  
4500' RTD

Surface Pipe: Set new  
8-5/8", 23# pipe @291'  
w/200 sacks 60/40 pozmix  
2% gel, 3% cc.

A F F I D A V I T

STATE OF KANSAS  
COUNTY OF BARTON) ss

Leonard Williamson of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

*Leonard Williamson*

Subscribed and sworn to before me this 11 day of November 1988.

*Dorothy M Hague*  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION

NOV 15 1988

CONSERVATION DIVISION  
Wichita, Kansas