

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Barber County, Sec. 8 Twp. 31s Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines NW NE NE

Lease Owner Santa-Fe Pipe & Supply, Inc.

Lease Name Gress Well No. 1

Office Address Box 562, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) gas

Date well completed 19

Application for plugging filed December 16 1968

Application for plugging approved December 17 1968

Plugging commenced December 17 1968

Plugging completed December 26 1968

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. R. J. Warren

Producing formation Depth to top Bottom Total Depth of Well 3900' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	244'	none
				4-1/2"	3879'	3201.86'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 3900' - 3750' - sand
- 3750' - 3714' - 3 sacks cement
- 3714' - 240' - mud
- 240' - 230' - rock bridge
- 230' - 155' - 25 sacks cement
- 155' - 40' - mud
- 40' - 30' - rock bridge
- 30' - base - 10 sacks cement

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Santa-Fe Pipe & Supply, Inc.,  
Address Box 562, Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
T. L. Nutt (employer/owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) T. L. Nutt

Box 562, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 25 day of January, 1969

Mary M. Guesnier Notary Public.  
My commission expires July 31, 1970



KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS

COPY

COMPANY JAMES W. HERSHBERGER

SEC. 8 T. 31 R. 12W  
 LOC. C NW NE NE

FARM Grass

NO. 1

TOTAL DEPTH 3900

COMM. 5-18-66

SHOT OR TREATED

CONTRACTOR White & Ellis


ISSUED 8-20-66

COMP. 5-29-66

RECEIVED  
 STATE CORPORATION COMMISSION

DEC 17 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

COUNTY Barber



CASINO

20 10  
 15 8 5/8" @ 244' w/135 SX.  
 12 6  
 13 8 4 1/2" @ 3879' w/100 SX.

ELEVATION 1823' KB

PRODUCTION CSO

FIGURES INDICATE BOTTOM OF FORMATIONS 4PT TST: 5,200 MCFGPD  
 (DOUG 3759-63) SIP 1215#

FORMATION	DEPTH
Open	0-9
Sand	125
Shale and red rock	252
Red rock	600
Red rock and shale	1225
Shale	1760
Lime and shale	1875
Lime	2210
Shale and lime	2300
Lime	2475
Lime w/shale stks.	2650
Lime	2815
Lime and shale	2988
Lime	3345
Shale w/lime stks.	3486
Lime	3489
Shale and lime	3530
Shale	3641
Shale and lime	3760
Sand	3802
Shale and lime stks.	3900

TOPS: SCOUT

Elgin	3542
Heebner	3698
Toronto	3715
Douglas Shale	3732
U/ " Sand	3759
B/ " "	3782
L/ " "	3838